

# Very Forward Proton Spectrometer VFPS @H1

## An Overview

- ▶ VFPS : purpose/location
- ▶ VFPS implementation
  - Cold bypass
  - Roman pot structure
  - Fiber Detector
- ▶ VFPS operation
  - Trigger & Readout
  - Roman pot controls / user interface
  - Roman pot movement
  - Some experiences ...
- ▶ Collected data /data quality
- ▶ First look onto analyses
  - Inclusive diffraction
  - Diffractive jets
- ▶ Momentum reconstruction
- ▶ Conclusions

# Purpose of VFPS

- Purpose VFPS

⇒ tagging of diffractive proton with

1. Large acceptance in  $x_p$
2. Full  $t$  coverage (down to  $t_{\min}$ )




- Complementary to FPS (H,V)

- Small acceptance in larger  $x_p$  range
- limited  $t$ -acceptance ( $0.08 < t < -0.5 \text{ GeV}^2$ )

- Location

- 3 possible locations
- Best acceptance in  $(x_p, t)$  @ 220 m
- Roman pots located
  - @ 218 m ⇒ VFPS1
  - @ 222 m ⇒ VFPS2



- VFPS location in cold HERA section



# VFPS Cold Bypass

## Bypass chronology

- 2000 first ideas to replace Roman pots cold ?
- Roman pots warm ?
- 2000-Nov design start (ext. firm)
- 2001-June end design (350 drawings)
- 2002-Febr Tenders out
- 2002-April Offers received
- 2002-May Starting construction (Dutch firm Demaco)
- 2002-Dec Shipping to DESY
- 2002-Dec Test bench DESY
  - He-Leak tests
  - Superconductors tests
  - ⇒ **successful**
- 2003-April Installation in HERA tunnel




# VFPS Cold bypass installed - 2003 April

## Bypass and associated elements

Ti-pump

Beam position monitor

Bypass connections:  
quadrupole side  
dipole side



quadrupole connection





dipole connection

# VFPS cold bypass

Hera tunnel:NL220m

Bypass design





# Roman pot structure

## Roman pot main elements

- Heidenhain rulers  
Ruler precision  $5 \mu$   
Range 120 mm
- Motor + movement transfer  
Motor step  $1/4 \mu$
- Pressure system for Roman pot ejection

Drag error  $80 \mu$


## Roman pot mounting platform



# Roman pot + detector insert


Detector elements: scintillating fibers

- fibers (roads) 5 staggered fiber planes  
2 planes (u,v)/pot  $\Rightarrow$  tracking  
Resolution  $100 \mu$
- tiles (tiles) 4 tiles/plane  
2 planes (u,v)/pot  $\Rightarrow$  triggering




Tiles(u,v)

Position/Temp sensor




Fibers(u,v)



## Roman pot window

Pot windows machined from one block  
(standard machining method)

Thickness  $\approx 300 \mu \pm 50 \mu$






# Trigger and Readout


- Trigger

- Tile signals (T1-T16) to 16 PM's
- Discriminated tile signals to programmable coincidence unit
- Trigger requires 1 signal in 3 out of 4 planes
- Trigger signal to H1 L1 trigger "air cable" ( $<2.3\mu s$ )


- Fiber signals



- 480 fiber signals to 8 PSPM's (16 pixels)
- Read by FPS/VFPS DAQ system over optical link



## VFPS/FPS Data Acquisition System




# FPS/VFPS Roman pot controls

Roman pot control system is VME-based  
(independent system)

- **Control/readout VMIC7750-CPU (+disk)**
  - Watch-Dog unit (control software running, temperature in limits) if not
    - ⇒ motor power cut ⇒ Roman pot ejected
  - Scalers ( detector rates, coincidences)
- CAN bus controller: CAN bus connected to
  - Motor controllers (6) - control/readout
  - Heidenhain rulers(6) - readout
  - Temperature modules(2) - readout

• **User communication VMIC7750-PVSS: TCP/IP**

1. PVSS ⇒ VMIC7750
  - Action requests
  - Updating of VMIC database
2. VMIC7750 ⇒ PVSS
  - Device status information
  - Messages of actions
  - Error messages



Data Logging PVSS

- Values all devices / 1-3 sec
- Messages actions/errors
- Machine parameters
- Beam position monitor

Database(VMIC)

Contains all constants for devices and movements

# PVSS: User displays


PVSS communicates with

1. VMIC
2. NETMEX (HERA)
3. VFPS slow control (HV)


PVSS logs all data

Roman pot (positions, temp,...), Hera (mag.,coll,...)


Stores logfiles



## PVSS main panel



## PVSS rates/position panel



• Detector position

• Detector rate

# VFPS operation: Roman pot movement

## Move-in condition

- Luminosity
- Scaler rates non zero




## Checks during move-in

- Average coincidence rates (sampling  $\approx 5$  meas.)
- Gradient rate
- Movement is halted when rate over limit
- Peak rate exceeded  $\rightarrow$  eject

## Target-in position


- Checking peak rate if exceeded  $\rightarrow$  eject

## FPS/VFPS Move-In Procedure



## VFPS operation: influence VFPS1 on VFPS2


- During move-in procedure
- Normal running




# VFPS operation: Effect of VFPS1 on VFPS2

- Effect on the hit multiplicity


### Tile multiplicity/plane VFPS1




### Total tile multiplicity VFPS1



### Tile multiplicity/plane VFPS2



### Total tile multiplicity VFPS2




# VFPS Running experience 2004-2007

2004


Irradiated fibers (trigger rate ↓)

2005

Detector shift in pot (access !!)  
Good data after June



VFPS/FPS Data Acquisition System





2006

Broken motor axis  
**Standard running**  
Various beam kicks


2007

**Standard running**



# Collected VFPS data


- 2004 startup period (fiber problem)
- 2005 detector fixing problem
  - 20 pb<sup>-1</sup>
- 2006
  - 95 pb<sup>-1</sup> 66%
- 2007 E=920 GeV
  - 12 pb<sup>-1</sup> 84%
- 2007 Low E
  - 3.9 pb<sup>-1</sup> 82%






# Data Quality: Tiles

## Tile 2 : Efficiency / DayOfYear






## Summary tile efficiencies



## Inclusive diffraction (T.Hreus)

- VFPS acceptance
  - $X_p$  as measured is H1
    - ⇒ Good acceptance in expected  $x_p$  region (Tile efficiency to be added)
- Statistics used  $24 \text{ pb}^{-1} = 80\text{K}$  ( $130 \text{ pb}^{-1}$ )
  - Proton beam bump @ 6mm
  - 3900 VFPS tagged events ( $n_{\text{max}} R_{\text{spac}}$  cut)
- Analysis  $F_2D_3$
- In conjunction with  $t$ -measurement
  - ⇒  $F_2D_4$





## Inclusive diffraction (T.Hreus)

- Event selection - H1 detector

1.  $|Z_{\text{vertex}}| < 40 \text{ cm}$
2.  $E_{\text{electron}} > 10 \text{ GeV}$
3.  $Q^2_{\text{electron}} > 10 \text{ GeV}$
4.  $E_x > 3 \text{ GeV}$
5.  $M_x > 3.5 \text{ GeV}$
6. Rapidity gap
  - Forward Muons  
 $\#F_{\mu}(P_1+P_2) < 2 \ \&\& \ \#F_{\mu}(p_1+p_2+p_3) < 3$
  - $\eta_{\text{MAX}} < 2.5$




- Event selection - VFPS tag

Trigger  
 $\text{vfps1te} \ \&\& \ \text{vfps2te}$   
 (vfps1te = 3 planes of 4 have  $\geq 1$  hit)





## Di-jet analysis - DIS (J.Delvax)

- Event selection - H1 ( $K_+$ -algorithm)
  - DIS cuts
  - $(P_{T,1}^* > 5 \text{ GeV}) \& (P_{T,2}^* > 4 \text{ GeV})$
  - $\eta_{J1,J2} \in [-1,+2]$
- Event selection VFPS
  - vfps1te && vfps2te
- Statistics:
  - $97\text{pb}^{-1}$  (75% of total event sample)
  - $\Rightarrow 637$  events
- VFPS tag selects di-jets with good acceptance




# Jet analysis - Photoproduction (J.Delvax)

- Event selection H1: 2 Jets (Kt-algorithm)
  - $\eta_{MAX} < 2.5$
  - $(P_{T,1}^* > 5 \text{ GeV}) \ \& \ (P_{T,2}^* > 4 \text{ GeV})$
  - $\eta_{J1,J2} \in [-1,+2]$
- Event selection VFPS
  - vfps1te & vfps2te
- Statistics  $23.7 \text{ pb}^{-1}$ 
  - Collected with dedicated trigger
  - total statistics 2006+2007  
6000 events
- **Goal**  
Compare t-dependence in  
DIS & Photo production jets  
(factorization breaking)




# Proton beam bumps for VFPS

Beampipe aperture limitation at 200 m  $\Rightarrow$  high  $x_p$  scattered protons are lost  
**Solution**  $\Rightarrow$  Introduce beam kick





Closed bumps for nominal protons  
 for diffractive protons ?


## Principle



## Practice: different bumps used 2006



# Momentum reconstruction diffractive proton (T.Sykora)




Beam Optics: find map:  $M^{-1}: (x_p, \theta, \varphi) \Leftrightarrow (x, y, y', y')$   
 - standalone  
 - H1SIM

Reconstruction: find map:  $M: (x, y, y', y') \Leftrightarrow (x_p, \theta, \varphi)$   
 - Neural Network


Calibration: Detector - beam distance

# MC versus data

## Detector x-y hit maps



MC






data






# Neural Net Reconstruction

$$\text{Minimize} \longrightarrow \sigma = \frac{1}{2} \sum (y_{\alpha,i}^{gen}(\vec{x}) - y_{\alpha,i}^{data}(\vec{x}))$$

Net Reconstruction





Generated  $\rightarrow$



## $x_p$ Reconstruction

1. Kinematic peak method: t-spectrum unbiased  $\langle \Theta_x \rangle = 0$   $\langle \Theta_y \rangle = 0$



2.  $p$  events kinematically fully defined ;  $e + p \Rightarrow e' + p + p'$   $p'$  is known from H1 acceptance in t 100 %  
(in progress)

# Conclusions

- VFPS hardware experience: (very) good except
  - irradiated fibers (unforeseeable)
  - Even small problems can turn out to be big because of limited tunnel access !
- VFPS software experience: (very) good
  - No major problems
  - Once properly adjusted to beam environment: fine
- VFPS ↔ HERA machine
  - Many parameters to survey: needs permanent attention
- Proton momentum Reconstruction: difficult because of many details to be taken into account (beam bumps)
- Analyses in progress and planned
  - $F_2D_3$  analysis based on VFPS trigger only
  - $F_2D_4$  analysis : follow-up of  $F_2D_3$  with t-measurement
  - Analysis of DIS/photo-produced jets with t-slope measurements

END